OFFICE OF THE PRESIDENT, DISTRICT BOARD, SHIMOGA.

Notification No. C. 98—L. B. 31-32, dated 27th April 1933.

Notice is hereby given that sealed tenders will be received at the Office of the President, District Board, Shimoga, up to 15th May 1933 (2 P.M.) for special repairs to Nyamthi-Arundi Road, Ayanur-Honnali District Fund Road to the Nyamthi Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of June 1933.

2. The detailed estimates may be seen at the District Board Office, Shimoga, between the hours of 11 A.M. and 5 P.M. on all working days.

3. Tenders should be accompanied by a statement in the from given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred only (Rs. 100) in cash or Government Promissory Notes, as earnest money and superscribed "Tenders for special repairs to Nyamthi-Arundi Road" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the President, District Board, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the President's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained or any account after acceptance of tenders.

11. The contractor will be dealt with in itmes of the bond for any short progress or delay. In matters of all disputes about rates, measurements, quantity of work, etc., the decision of the President will be final and legally binding on the contrator.

Abstract estimate of quantities for the special repairs to Nyamthi-Arundi Road.

Name of work	Unit	Quantity	Rate	Amount
1. Picking the road surface	Cyd.	315		
2. Collection of rough metal	...	210		
3. Spreading, forming with consolidation ...	...	210		
4. Two and a half miles lead	...	210		
5. Collecting burnt size metal	...	165		
6. Spreading forming with consolidation ...	...	165		
7. Two and a half miles lead	...	165		
8. Gravel collection for with spreading, forming, consolidation and ½ mile lead	...	100		
9. Excavating the drain	Cyds.	33		
10. Construction of drain with size stone in mortor. Two in number	C.fts.	225		
11. Old stone slabs (lay over the drain), (*i.e.*, existing slabs)	...	...		
12. Parapet walls to support the both side drains with size stone in mortor	C.fts.	64		
13. New stoneslabs to lay over the parapet walls and to the sides.	Sq.ft.	72		
14. Plastering chunnam painting to the parapet walls	...	...		

H. SIDDAIYA,
President.